



4305 - SPECIFICATION FOR TRAFFIC GRAVEL BEHIND CONSTRUCTION

4305.1 DESCRIPTION

- 4305.1.1 The Work shall consist of traffic gravel placed and spread on a newly constructed subgrade surface at the locations shown on the Plans or as designated by the Engineer.

4305.2 MATERIALS

- 4305.2.1 The traffic gravel may be obtained from Ministry stockpile(s) shown on the Plans and/or as stated in the Special Provisions.

4305.3 CONSTRUCTION

- 4305.3.1 Traffic gravel shall be hauled in accordance with Specification 2405 For Haul On The Basis Of The Kilometre.
- 4305.3.1.1 The Engineer may permit the use of motor scrapers for hauling traffic accommodation gravel providing that no damage results to the subgrade surface due to the heavy loads.
- 4305.3.2 Traffic gravel shall not be deposited until the subgrade surface has been trimmed and accepted in writing by the Engineer. Traffic gravel shall be dumped and spread uniformly on the subgrade surface at the rate specified in the Contract or as designated by the Engineer. The Contractor shall commence placing traffic gravel within 6 hours of receiving acceptance of the subgrade surface.
- 4305.3.3 Traffic gravel shall be deposited and spread so that at no time shall there be more than 5 kilometres of graded or partly graded subgrade not covered with gravel.
- 4305.3.4 Traffic gravel shall be applied to the finished surface of designated approaches and detours as directed by the Engineer.
- 4305.3.5 Traffic gravel shall be applied during periods of inclement weather on isolated areas within the construction zone. The Contractor shall be prepared to commence placing traffic gravel on any section of the subgrade under construction within 1 hour if so directed by the Engineer.
- 4305.3.6 If work must be carried over from one construction season to the next, traffic gravel shall be placed on all graded or partly graded sections of subgrade.

4305.4 MEASUREMENT

- 4305.4.1 Traffic Gravel Behind Construction will be measured in the vehicle in cubic metres or in tonnes to the nearest 0.1 of a cubic metre or tonne.

4305.5 PAYMENT

- 4305.5.1 Payment for Traffic Gravel Behind Construction will be at the contract unit price per cubic metre or tonne. The unit price will be full compensation for loading, hauling, dumping, and spreading the gravel.