



6015.1 DESCRIPTION

- 6015.1.1 The work shall consist of the installation of silt fence to prevent sediment, debris and foreign material from entering a waterbody as a result of the Work.

6015.2 MATERIALS

- 6015.2.1 The Ministry will supply the silt fence material.

6015.3 CONSTRUCTION

- 6015.3.1 Silt fence shall be installed prior to any ground surface being disturbed unless otherwise directed by the Engineer.
- 6015.3.2 Silt fence shall be installed at locations required to comply with any regulatory agency requirements, and/or as indicated on the Plans, and/or as directed by the Engineer.
- 6015.3.3 Silt fence shall be installed in accordance with the manufacturer's recommendations or as directed by the Engineer.
- 6015.3.4 The Contractor shall be responsible for monitoring, maintaining and repairing the silt fence until Final Acceptance of the Contract.
- 6015.3.4.1 The Contractor shall ensure that loading on the silt fence does not exceed loading limits. Material removed from the silt fence shall be disposed of as directed by the Engineer.
- 6015.3.4.2 The silt fence shall be free from trapped material at the time of Final Acceptance.
- 6015.3.4.3 All work associated with monitoring, maintaining and repairing, including the removal and disposal of material trapped by the silt fence, will not be paid for directly but will be considered as a subsidiary obligation of the Contractor under this Contract.
- 6015.3.5 The Contractor shall repair or replace, at no direct expense to the Ministry, any fence material damaged by their operations.
- 6015.3.6 Silt fence shall remain in place at the completion of the Contract unless otherwise directed by the Engineer.

6015.4 MEASUREMENT

- 6015.4.1 Install Silt Fence will be measured in lineal metres.

6015.5 PAYMENT

- 6015.5.1 Payment for INSTALL SILT FENCE will be at the contract unit price per metre. The unit price will be full compensation for completing the work.