



**6025.1 DESCRIPTION**

- 6025.1.1 The work shall consist of seeding all disturbed areas and other areas of the Project as designated by the Engineer.

**6025.2 MATERIALS**

- 6025.2.1 The Ministry will supply the seed material.

**6025.3 CONSTRUCTION**

- 6025.3.1 Prior to seeding, the area to be seeded shall be true to grade and cross section and free from irregularities.
- 6025.3.2 Designated areas shall be uniformly seeded as directed by the Engineer.
- 6025.3.3 The rate of application will be determined by the Engineer.
- 6025.3.4 Seeding shall be completed within the seeding periods outlined in the Special Provisions unless otherwise authorized by the Engineer.
- 6025.3.4.1 Daily liquidated damages will not be assessed outside the specified seeding periods provided all other Contract Items are completed.
- 6025.3.5 The Contractor shall harrow the seeded areas immediately after the seeding is completed.
- 6025.3.6 The Contractor shall repair and re-seed, at no direct expense to the Ministry, any seeded areas disturbed and/or damaged by their operations.

**6025.4 MEASUREMENT**

- 6025.4.1 Seeding will be measured in hectares determined from horizontal measurements.
- 6025.4.1.1 The area will be calculated to the nearest 0.01 of a hectare.

**6025.5 PAYMENT**

- 6025.5.1 Payment for SEEDING will be at the contract unit price per hectare. The unit price will be full compensation for completing the work.