



6215 - SPECIFICATION FOR GUIDE POSTS

6215 - 1 DESCRIPTION

- 1.01 The work shall consist of metal and wooden guide posts, including highway delineators, installed at the locations and in conformity with the dimensions and other details shown on the plans or as designated by the Engineer.

6215 - 2 MATERIALS

- 2.01 Material for guide posts will be supplied and paid for by the Department.

6215 - 3 CONSTRUCTION

- 3.01 The Contractor shall repair or replace, at no direct expense to the Department, any guide post material damaged by his operations.
- 3.02 If untreated posts are supplied, the Contractor shall treat the butt of each post with a wood preservative. The work shall be performed on an Extra Work basis.
- 3.03 The surface cross section of the road shall be completed before the guide posts are installed.
- 3.04 The hole for the wooden post shall be of sufficient size to provide a clear distance of five centimetres (5 cm) around the post.
- 3.05 Posts shall be set plumb and shall conform to the alignment staked.
- 3.06 The spaces around the posts shall be backfilled with earth material, free of large stones. The backfill material shall be placed in layers not exceeding fifteen centimetres (15 cm) in depth and shall be firmly tamped. If required, water may be used to aid compaction.
- 3.07 If soil conditions permit, the metal posts may be driven by hand or mechanical methods.
- 3.08 If painting is included on the tender form, wooden posts shall be coated with two (2) coats of paint and metal posts shall be coated with one (1) application of paint. Paint shall be applied after the post holes have been backfilled.
- 3.09 Metal targets and reflector units shall be attached after the posts have been painted.

6215 - 4 MEASUREMENT

- 4.01 Each guide post will be measured as a unit.

6215 - 5 PAYMENT

- 5.01 Payment for each GUIDE POST will be at the contract unit price per post. The unit price will be full compensation for unloading, storing, handling, and hauling materials; excavating holes; placing posts; placing, watering, and tamping the backfill material; and attaching metal targets and/or reflector units. If painting is included on the tender form, the unit price will be full compensation for painting the posts.