

2160 – SPECIFICATION FOR REMOVAL OF FENCE

2160.1 DESCRIPTION

2160.1.1 The Work shall consist of the removal of fences and fabricated gates shown on the Plans or designated by the Engineer and the disposal of fence materials not suitable for re-use.

2160.1.2 Fabricated gates will not include Texas gates.

2160.2 CONSTRUCTION

2160.2.1 Fences shall not be removed until written instructions have been issued by the Engineer. Fences affecting the moving of power and telephone lines shall be removed within 14 days of receiving written instruction.

2160.2.2 All removed fence materials shall become the property of the Contractor.

2160.2.3 Non-useable fence materials shall not be disposed of without the consent of the landowner.

2160.2.4 Non-useable fence materials, which the landowner does not wish to retain, shall be hauled to a disposal site(s) selected by the Contractor.

2160.2.4.1 All disposal sites shall be the responsibility of the Contractor.

2160.2.4.2 The Contractor shall ensure that the disposal site(s) complies with all Federal and Provincial laws and regulations, and all local bylaws, ordinances and regulations prior to disposing of the materials.

2160.3 MEASUREMENT

2160.3.1 Removal Of Fence will be measured in metres.

2160.3.2 Length will be determined from horizontal measurements.

2160.4 PAYMENT

2160.4.1 Payment for Removal Of Fence will be at the contract unit price per metre. The unit price will be full compensation for completing the Work.

2160.4.2 Payment for removal of Texas gates will be on an Extra Work basis.