

2165 – SPECIFICATION FOR REMOVAL OF CONCRETE CURBS, SIDEWALKS, AND DRIVEWAYS

2165.1 DESCRIPTION

- 2165.1.1 The Work shall consist of the removal and disposal, in whole, or in part, of concrete curbs, curb and gutter, sidewalks, and driveways shown on the Plans or designated by the Engineer.

2165.2 CONSTRUCTION

- 2165.2.1 If a section of sidewalk or curb is to be removed it shall be separated from, and without damage to, the section that is to remain. No explosives shall be used.
- 2165.2.2 The section of curb, curb and gutter, sidewalk, and driveway to be removed will be staked by the Engineer.
- 2165.2.3 Debris shall be disposed of as follows:
- 2165.2.3.1 If earth embankments are to be constructed as part of the Contract, the debris may be used in the embankments in accordance with Specification 2300 For Embankments; or
 - 2165.2.3.2 The debris may be hauled to a disposal site(s) selected by the Contractor.
 - 2165.2.3.2.1 All disposal sites shall be the responsibility of the Contractor.
 - 2165.2.3.2.2 The Contractor shall ensure that the disposal site(s) complies with all Federal and Provincial laws and regulations, and all local bylaws, ordinances and regulations prior to disposing of the debris.

2165.3 MEASUREMENT

2165.3.1 Removal Of Concrete Sidewalks And Driveways will be measured in square metres. The actual surface area will be measured.

2165.3.2 Removal Of Concrete Curbs will be measured in metres along the front face of the curb.

2165.4 PAYMENT

2165.4.1 Payment for Removal Of Concrete Sidewalks And Driveways will be at the contract unit price per square metre. The unit price will be full compensation for completing the Work.

2165.4.2 Payment for Removal Of Concrete Curbs will be at the contract unit price per metre. The unit price will be full compensation for completing the Work.